

2605 Samoa Dr.

Zoning Board of Adjustment — March 10, 2025



CASE NUMBER: PZBA25-00007
CASE MANAGER: Blanca Perez, (915) 212-1561, PerezBM@elpasotexas.gov
PROPERTY OWNER: Molly and Jason Arriola
REPRESENTATIVE: Vanessa Duran
LOCATION: 2605 Samoa Dr. (District 3)
ZONING: R-3 (Residential)
REQUEST: Special Exception J (Carport Over a Driveway)
PUBLIC INPUT: None received as of March 4, 2025.

SUMMARY OF REQUEST: Applicant requests a Special Exception under Section 2.16.050 J (Carport Over a Driveway) to allow to legalize an existing carport over a driveway in an R-3 (Residential) zone district.

SUMMARY OF STAFF'S RECOMMENDATION: Staff recommends **APPROVAL WITH CONDITIONS** of the special exception request as the requested area of encroachment is less than the maximum permitted for a carport. The conditions are as follows:

1. Accessory structure shall be removed or relocated from the five-foot utility easement area.
2. For the finalized carport to resemble the main residential structure as shown on elevations.

PZBA25-00007




Figure A. Aerial of Subject Property & Immediate Surroundings

DESCRIPTION OF REQUEST: The applicant is requesting a special exception to legalize the construction of an existing carport of approximately 20 feet 5 inches by 20 feet and an area of 408 square feet, of which 198 square feet encroaches 9 feet 8 ½ inches into the front yard setback and is located to within 10 feet 3 ½ inches of the front property line.

BACKGROUND: The minimum front setback is 20 feet in the R-3 (Residential) zone district. The required front setback for the subject property is 20 feet to meet the cumulative front and rear setback of 50 feet in the R-3 (Residential) zone district.

According to the El Paso Central Appraisal District records, the home was built in 1959 and the current owner has owned the home since 2024. The encroachment was built by the current owner in 2024 and the request is due to a code enforcement citation.

SETBACKS	REQUIRED SETBACK	REQUESTED SETBACK
Front	20 Feet	10 Feet 3 ½ Inches
Rear	30 Feet	No Change
Cumulative Front & Rear	50 Feet	40 Feet 3 ½ Inches
Side (Right)	5 Feet	No Change
Side (Left)	5 Feet	No Change
Cumulative Side	N/A	N/A

CALCULATIONS FOR CARPORT:

	TOTAL	CALCULATION
Maximum Permitted Area of Encroachment	347.8 Square Feet	1/5 of 1739 Sq. Ft. (House 1 st floor area)
Requested Area of Encroachment	198 Square Feet	9.71 Feet by 20.42 Feet (Encroachment only)

COMPLIANCE WITH SPECIAL EXCEPTION 2.16.050.J CRITERIA

The Zoning Board of Adjustment is empowered under Section 2.16.050.J to:

Permit the encroachment into the required front yard setback for a lot in a residential (R) district beyond other allowed modifications for a carport covering a driveway, provided the following criteria is met:

Criteria	Does the Request Comply?
1. The residence has been in existence with a valid certificate of occupancy for one continuous year;	Yes. The residence has a valid certificate of occupancy for one continuous year.
2. The zoning board of adjustment has received the written approval of the structural design from the building official;	Yes. The Building Official has reviewed the request, and has provided written approval.
3. The carport shall resemble the main residential structure in scale and character and shall be open on three sides;	Yes. The existing carport will resemble the main residential structure and is open on three sides.
4. The area of the carport shall not exceed one-fifth of the first-floor area under roof of the dwelling, with the first-floor area of the dwelling defined as the sum of the gross horizontal area, exclusive of garages, atriums, stairwells, and open porches, measured from the exterior faces of the exterior walls; and, shall be measured as the area covered by the carport roof, to include overhangs;	Yes. The existing carport encroachment of 198 square feet is less than the maximum allowed area of 347.8 square feet.
5. Elevation drawings of the proposed structure shall be submitted;	Yes. Elevation drawings of the existing structure were submitted.
6. For a duplex, the total of all extensions for either unit of the duplex shall not exceed two-thirds of the average width of that unit;	Not applicable. This is not a duplex.

7. There is no other reasonable alternative to provide a carport in the front yard of the subject property without exceeding the encroachments allowed in Title 20 of this Code;	Yes. It is not possible to provide a carport in the front yard without encroaching into the required front setback.
8. Unless otherwise provided in this chapter, all remaining areas of the required front yard shall be permanent open space.	Yes. With the exception of any existing structures, remaining area shall be permanent open space

PUBLIC COMMENT: Public notice was sent on February 27, 2025 to all property owners within 300 feet of subject property. The Planning Division has not received any communications in support or opposition to the special exception request.


ZONING BOARD OF ADJUSTMENT OPTIONS:

The purpose of the Zoning Ordinance is to promote the health, safety, morals and general welfare of the City. The Zoning Board of Adjustment (ZBA) has the authority to grant a special exception to the zoning code only as provided in El Paso City Code Titles 2 and 20. In evaluating the request, the ZBA may take any of the following actions:

1. **Approval** of the special exception request, finding that the request is in in harmony with the spirit and purposes of Titles 2 and 20, including the preservation of the essential character of the district in which the property is located, that the public convenience and welfare will be substantially served, and that the use of neighboring property will not be substantially injured.
2. **Approval with Modifications** of the special exception request to bring the request into conformance as provided in El Paso City Code Titles 2 and 20 as the board deems appropriate. **(Staff Recommendation)**
3. **Denial** of the special exception request, finding that the request does not conform to the review criteria as provided in El Paso City Code Titles 2 and 20.

ZONING MAP

PZBA25-00007



This map is designed for illustrative purposes only. The features depicted here are approximate and more site-specific studies may be required to draw accurate conclusions. Enlargements of this map to scales greater than its original can induce errors and may lead to misinterpretations of the data. The Planning & Inspections Department Planning Division makes no claim to its accuracy or completeness.




Subject Property

0 10 20 40 60 80 Feet



NEIGHBORHOOD NOTIFICATION MAP

PZBA25-00007



This map is designed for illustrative purposes only. The features depicted here are approximate and more site-specific studies may be required to draw accurate conclusions. Enlargements of this map to scales greater than its original can induce errors and may lead to misinterpretations of the data. The Planning & Inspections Department Planning Division makes no claim to its accuracy or completeness.




Subject Property
 300 Feet Notice Area
 Notified Properties


0 30 60 120 180 240 Feet



SITE PLAN



ELEVATION 1



ELEVATION 2

