CITY OF EL PASO, TEXAS **AGENDA ITEM** DEPARTMENT HEAD'S SUMMARY FORM

AGENDA DATE: PUBLIC HEARING DATE:	March 12, 2024
CONTACT PERSON(S) NAME AND PHONE NUMBER:	Yvette Hernandez, P.E., City Engineer, 212-0065
DISTRICT(S) AFFECTED:	District 3
STRATEGIC GOAL:	No. 4: Enhance El Paso's Quality of Life
SUBGOAL:	4.2 Create innovative recreational, educational and cultural program

SUBJECT:

Discussion and action on the award of Task Order 1 for solicitation 2023-0397, August 3rd Memorial project to Keystone GC, LLC. for a total estimated award of \$632,741.02.

BACKGROUND / DISCUSSION:

Work under these contracts is performed via task orders with task orders exceeding FIVE HUNDERED THOUSAND DOLLARS (\$500,000) requiring Council approval. The task order for the Health Department Relocation Railroad project exceeds \$500,000 and therefore requires Council approval. Scope includes installation of a 4" concrete plaza, sandblasted concrete, concrete benches, concrete curbs, concrete footings for new art sculptures, new irrigation system, new landscaping, new electrical lighting, and a new HMAC walking path that is a length of approximately 0.12 miles. Demolition of existing trees, concrete slab, existing chat path, concrete curb, concrete sidewalk, decorative wall/structure, signs with all appurtenances, and all items that interfere with the proposed improvements.

PRIOR COUNCIL ACTION:

2023-0397: Horizontal Construction Improvements (January 10, 2024)

AMOUNT AND SOURCE OF FUNDING: \$632.741.02 funded by Public Art (Provided by MCAD)

HAVE ALL AFFECTED DEPARTMENTS BEEN NOTIFIED? ☑ YES □NO

PRIMARY DEPARTMENT: CID SECONDARY DEPARTMENT: MCAD

DEPARTMENT HEAD:

Gvette Hernandez (If Department Head Summary Form is initiated by Purchasing, client department should sign also)

CITY OF EL PASO CONSTRUCTION CHANGE ORDER

CONSTRUCTION CHAN	GE ORDER NO.:	1	DATE:	February 26, 2024		SCOPE CHANG	E
PROJECT:	Aug	gust 3rd Memorial		SOLICITATION #	2023-0397	X CONSTRUCTION	N CHANGE
	Original Contr	ract Amount:	\$632,741.02		Contract Time to Subs	tantial Completion	72
Net	t Change by previous Cha	ange Orders:	\$0.00	Total days	s added due to Change	Orders and CQN's	0
Net Change by pr	evious Construction Quar	ntity Notices:	\$0.00		Total days added for	this Change Order _	0
Amou	unt of this Construction Ch	ange Order:	\$632,741.02	New	/ Contract Time to Subst	antial Completion:	72
	New Amended Contr	ract Amount:	\$632,741.02		Current Substantial Cor	mpletion Due Date	June 5, 2024
Change Order Percenta	age:		0.00%				
CONTRACTOR NAME:	Key	stone GC, LLC		Fundin	ng Source	MCAD	

Please provide a detailed scope of work of the change order (see back for reason/justification):

This change order is to incorporate construction documents into the 2023-0397 Horizontal Construction Improvements Contract No. 2023-0397 dated 01/10/2024.

In addition, this change order is to use the contract-Solicitation 2023-0397 Horizontal Construction Improvements dated 01/10/2024 for the scope of work of August 3rd Memorial project mentioned below.

Construction will conform to the General Conditions, Supplemental Conditions, and all Specifications included in the 2023-0397 Horizontal Construction Improvements Contract No. 2023-0397

August 3rd Memorial: Project Improvements

The contractor is to provide all labor, material, and equipment for the installation of a 4" concrete plaza, sandblasted concrete (Brush/Light, Medium, and Medium-Heavy), concrete benches, concrete curbs, concrete footings for new art sculptures, new irrigation system, new landscaping, new electrical lighting, and a new HMAC walking path that is a length of approximately 0.12 miles. Demolition of existing trees, concrete slab, existing chat path, concrete curb, concrete sidewalk, decorative wall/structure, signs with all appurtenances, and all items that interfere with the proposed improvements. The signage and fence to be coordinated and salvaged to MCAD at desired location at no additional expense. All other demolished items to become the property of the contractor and are required to be disposed to an approved location at no additional cost to the owner.

The project location is the SE side of Ponder Park located at the intersection of Sun Mount Drive and Viscount Avenue. The project is bounded by residential properties, Burges High School, Sun Ridge Assisted Living Center, Sun metro Bus stops, Cielo Vista Mall, and companies. An existing 85' drainage channel maintained by Parks is located on the east side of the project, located on the Sun Mount Drive side.

<u>Cost/item breakdown for project</u> Cost/item breakdown is included in Appendix A August 3rd Memorial Project's Construction Documents & Specifications are included in Appendix B Substantial completion Time: June 5, 2024 Final Completion Time: July 5, 2024 Cost: \$632,741.02					
CALENDAR DAYS A	DDED TO COMPLETION TIME: 0	TOTAL CHANGE ORDER AMOUNT:	\$632,741.02		
CONTRACT	ſOR				
I,	Francisco/Guillen, Principal, of	Keystone GC, LLC ag	ree and accept the terms		
Signature:	and conditions of this change order.	Date: F	ebruary 26, 2024		
CITY OF EL	- PASO (OWNER)				
	I, <u>Yvette Hernandez</u> of the City of El Paso hereby authorize and in this form.	I direct the Contractor to proceed with additiona	work as described		
Signature	e: <u>Gvette Hernandez</u> Yvette Hernandez	Date:	2/26/24		

CIT	Y OF EL PASO CON	ISTRUCTION CHANGE ORDER- Pg	. 2
NSTRUCTION CHANGE ORI	DER NO.: <u>1</u> August 3rd Memorial		OPE CHANGE
Purchase Order No.	TBD		
AS A R	ESULT OF THIS CHANGE ORDER, PLE	ASE MAKE THE FOLLOWING ADJUSTMENT TO THE PURCHASE OR	DER:
LINE	ADDED AMOUNT		
1-1	\$632,741.02	TOTAL NET CHANGE TO PURCHASE ORDER	
		\$632,741.02	
		(should match cost below)	
		(Should match cost below)	
		Additional funding/dir	ection:
		PBARTQLMCD8	35
		Department: 45	4
		Fund: 4005	
		Division: 54320	
		Program: P5499	9
son/Justification for chang k Order to incorporate the tract No. 2023-0397 date		nd construction documents into the 2023-0397 Horizontal Constr the overall contract amount.	ruction Improvements
	Project Manager recommends app	proval: Monica Humphrey for	2/26/20
		proval: <u>Monica Humphrey</u> for Manuel Miranda Martinez proval: <u>Daniel Garcia</u> Daniel Garcia	Date 2/26/202 4
Assistant Director for Constru	uction and development recommends app	Daniel Garcia	Date
		-	



Capital Improvement Department

WORK PROPOSAL

DATE SENT:		PROPOSAL NO.:		
February 15, 20	24	PR24- 07		
ATTENTION:				
Manuel E. Mirar	nda Mart	inez		
JOB LOCATIONS: POR	JOB LOCATIONS: Ponder Park			
500 W H Burges	5 Dr, El F	Paso, TX 79925		
JOB NAME August	3 rd Mem	orial – Horizontal		
Construction Improvement Contract				
PHONE	FAX/ EMA	IL		
(915)979-7960	Martine	ezME1@elpasotexas.gov		

218 N. Campbell St.

El Paso, Texas 79901

DESCRIPTION OF WORK:

We propose to furnish all labor, material, and equipment necessary for the following work, as per plans by In*suit Architecture dated December 21, 2023:

Demolition

STREET

- Provide and install temporary chain-link fence.
- Site concrete demolition to include, Concrete pad. Sidewalk, concrete curb.
- Landscaping demolition to include, tree removal, screening removal.
- Misc. Demolition to include, Signage, wrought iron fence.
- Load and haul off spoils from premises.

Earthwork

- Provide and install silt fence.
- Cut dirt and stockpile to accommodate new improvements.
- Engineering fill import, screening, and processing of materials.
- Subgrade preparation and compaction
- Load and haul off dirt from the premises.
- Removal of the silt fence.

Site Improvements

- Subgrade preparation for the new sidewalk.
- Finish or fine grading under proposed structures.
- Furnish and install vapor barrier under the proposed slab.
- Artistic concrete, 4" thick, color, and finishes to be selected by the owner, based on Bomanite selection.
- Construction of two (2) long benches mirror images of each other, as per plans.
- Construction of fourteen (14) small benches as per plans.
- Construction of seven (7) pedestals
 - Construction of mow strip curb as per landscape plans.
 - Apply curing compound on sidewalks.
- New 1-1/2" thick asphalt paving at the improvement area of the walking trail, as per plans.
- Four-inch liquid Thermoplastic Traffic Marking Paint by SealMaster layout as per plans.

Irrigation and Landscape

- Preserve, protect, and fill areas as needed, as shown on plans.
- Provide and install irrigation system as per plans.
- Provide and install new trees and 150 shrubs.
- Furnish and install bone river rock mix.
- Repair sod affected by construction as needed to match existing conditions.
- Apply herbicide to rock areas.
- Preserve and protect trees.

Electrical Improvements

- Furnish and install all electrical systems and lighting fixtures as per plans, to include the following:
 - 10-amp panel, 20 am breakers. The meter can, nema3r enclosures Provide, nema3r enclosure panel.

- Electrical rough-in material, electrical conduit wiring, necessary excavation and backfilling to set proposed conduit as per electrical plans.
- Lighting contactors, time clock, anti-graffiti concrete service poles.

Sub-Total	\$ 617,561.19
Construction permit, if not waived	\$ 3,085.32
Payment & Performance Bonds	\$ 12,094.51
Total Estimate	\$ 632,741.02
	· ·

Exclusions:

1. Any other material or work not directly expressed in this proposal.

Should you have any questions, do not hesitate to contact us. Sincerely,

Francisco Guillen, P.E. Keystone Contractors & Engineers Office: (915) 562-4159 x 23 Fax: (915) 503-2235 Email: fguillen@keystone-ce.net71

KEYSTORS & ENGINEERS

City of El Paso

El Paso, TX, 79925

7500 W H Burges Drive

August 3rd Memorial 2-15-24

KEYSTONE

Year 2024

Unit Detail Report by WBS

Prepared By: Jesus Campos

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Category: August 3rd Memori	al 2-15-24 > Demolition				
024113175300	Demolish, remove pavement & curb, remove concrete, rod reinforced, to 6" thick, excludes hauling and disposal fees	282.00	S.Y.	\$26.37	\$7,436.34
024113176000	Demolish, remove pavement & curb, remove concrete curbs, plain, excludes hauling and disposal fees	64.00	L.F.	\$6.76	\$432.64
024113300890	Minor site demolition, fence/guiderail removal, minimum labor/equipment charge	1.00	Job	\$321.78	\$321.78
024119193080	Selective demolition, rubbish handling, loading & trucking, machine loading truck, includes 2 mile haul, cost to be added to demolition cost	50.00	C.Y.	\$31.64	\$1,582.00
100505104020	Signs, traffic sign removal, to 10 S.F., including supports	2.00	Ea.	\$174.62	\$349.24
311313202040	Selective clearing and grubbing, 1-1/2 C.Y. excavator, 4" to 6" diameter, stump removal on site by hydraulic excavator	1.00	Ea.	\$62.78	\$62.78
311313203050	Selective clearing and grubbing, up to 6" diameter, remove selective trees, on site using chain saws and chipper, excludes stumps	1.00	Ea.	\$351.95	\$351.95
312323201038	Cycle hauling(wait, load, travel, unload or dump & return) time per cycle, excavated or borrow, loose cubic yards, 15 min load/wait/unload, 12 C.Y. truck, cycle 10 miles, 20 MPH, excludes loading equipment	65.00	L.C.Y.	\$15.95	\$1,036.75
Category: August 3rd Memori	al 2-15-24 > Demolition Subtotal				\$11,573.48
Category: August 3rd Memori	al 2-15-24 > Earthwork				
015626500250	Temporary fencing, chain link, rented up to 12 months, 6' high, 11 ga, over 1000'	2,000.00	L.F.	\$5.78	\$11,560.00
310516100600	Aggregate for earthwork, select structural fill, spread with 200 HP dozer, includes load at pit and haul, 2 miles round trip, excludes compaction	291.00	L.C.Y.	\$27.16	\$7,903.56
311413231520	Topsoil stripping and stockpiling, loam or topsoil, remove and stockpile on site, by skid steer, 101-500 S.Y., 6" deep, 100' haul	2,134.00	S.Y.	\$4.80	\$10,243.20
312213200160	Rough grading sites, 8,100-10,000 S.F., skid steer & labor	1.00	Ea.	\$3,471.46	\$3,471.46

Date: 02/15/2024

RSMeans data

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
312216101050	Fine grading, fine grade for small irregular areas, to 15,000 S.Y.	2,071.00	S.Y.	\$3.92	\$8,118.32
312323201038	Cycle hauling(wait, load, travel, unload or dump & return) time per cycle, excavated or borrow, loose cubic yards, 15 min load/wait/unload, 12 C.Y. truck, cycle 10 miles, 20 MPH, excludes loading equipment	505.00	L.C.Y.	\$15.95	\$8,054.75
312323235020	Compaction, riding, vibrating roller, 3 passes, 6" lifts	617.00	B.C.Y.	\$0.45	\$277.65
312323239010	Compaction, water for, 3,000 gallon truck, 6 mile haul	617.00	B.C.Y.	\$2.76	\$1,702.92
312514161000	Synthetic erosion control, silt fence, install and remove, 3' high	2,000.00	L.F.	\$3.64	\$7,280.00
Category: August 3rd Memorial 2	2-15-24 > Earthwork Subtotal				\$58,611.86
Category: August 3rd Memorial 2	-15-24 > Concrete				
031113854000	C.I.P. concrete forms, wall, radial, smooth curved, job built plywood, to 8' high, 1 use, includes erecting, bracing, stripping and cleaning	1,300.00	SFCA	\$12.69	\$16,497.00
032111600500	Reinforcing steel, in place, footings, #4 to #7, A615, grade 60, incl labor for accessories, excl material for accessories	4.50	Ton	\$2,908.68	\$13,089.06
033113350150	Structural concrete, ready mix, heavyweight, 3000 psi, includes local aggregate, sand, Portland cement (Type I) and water, delivered, excludes all additives and treatments	55.00	C.Y.	\$152.91	\$8,410.05
033113350150	Structural concrete, ready mix, all lightweight aggregate, add	1.00	C.Y.	\$68.81	\$3,784.52
033113702650	Structural concrete, placing, spread footing, pumped, over 5 C.Y., includes leveling (strike off) & consolidation, excludes material	50.00	C.Y.	\$24.72	\$1,236.00
033713601040	Provide and install concrete 3/8" aggregate, 3000-PSI, with sandblasted finish.	7,850.00	S.F.	\$23.50	\$184,475.00
033923130300	Concrete surface treatment, curing, sprayed membrane compound	87.00	C.S.F.	\$24.18	\$2,103.66
072613101200	Vapor retarders, building paper, polyethylene vapor barrier, standard, 10 mil (.010" thick)	87.00	Sq.	\$28.23	\$2,456.01
312316132300	Excavating, trench or continuous footing, hardpan, trim sides and bottom for concrete pours, excludes sheeting or dewatering	513.00	S.F.	\$2.63	\$1,349.19
312316166030	Structural excavation for minor structures, bank measure, for spread and mat footings, elevator pits, and small building foundations, common earth, 1/2 C.Y. bucket, machine excavation, hydraulic backhoe	34.00	B.C.Y.	\$33.28	\$1,131.52
Category: August 3rd Memorial 2	2-15-24 > Concrete Subtotal				\$234,532.01
Category: August 3rd Memorial 2	-15-24 > Paving				
312216101200	Fine grading, fine grade granular base for sidewalks and bikeways	590.00	S.Y.	\$1.52	\$896.80
312323201038	Cycle hauling(wait, load, travel, unload or dump & return) time per cycle, excavated or borrow, loose cubic yards, 15 min load/wait/unload, 12 C.Y. truck, cycle 10 miles, 20 MPH, excludes loading equipment	216.00	L.C.Y.	\$15.95	\$3,445.20
321123232010	Base course drainage layers, aggregate base course for roadways and large paved areas, alternate method to figure base course, crushed stone, 3/4"maximum size, 3" deep	150.00	Ton	\$27.90	\$4,185.00

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
321123232010	Base course drainage layers, aggregate base course for small and irregular areas, add	1.00		\$4.14	\$621.00
321216131260	Plant-mix asphalt paving, for turnouts and driveway entrances, wearing course, 1-1/2" thick, no hauling included	590.00	S.Y.	\$8.94	\$5,274.60
321216143000	Asphaltic concrete paving, parking lots & driveways, pre-treatment for paving, prime coat, emulsion, 0.30 gallons/S.Y., 1000 S.Y.	590.00	S.Y.	\$3.04	\$1,793.60
321723130020	Painted pavement markings, acrylic waterborne, white or yellow, 4" wide, less than 3,000 LF	660.00	L.F.	\$0.36	\$237.60
321723140790	Pavement markings, layout of pavement marking	660.00	L.F.	\$0.09	\$59.40
Category: August 3rd Memo	rial 2-15-24 > Paving Subtotal				\$16,513.20
Category: August 3rd Memo	rial 2-15-24 > Irrigation				
221113741880	Pipe, plastic, PVC, 1" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	528.00	L.F.	\$18.25	\$9,636.00
221113741890	Pipe, plastic, PVC, 1-1/4" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	414.00	L.F.	\$22.32	\$9,240.48
221113741900	Pipe, plastic, PVC, 1-1/2" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	409.00	L.F.	\$24.83	\$10,155.47
221113741910	Pipe, plastic, PVC, 2" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	59.00	L.F.	\$27.38	\$1,615.42
221113741920	Pipe, plastic, PVC, 2-1/2" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	22.00	L.F.	\$31.36	\$689.92
221113741930	Pipe, plastic, PVC, 3" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	10.00	L.F.	\$37.09	\$370.90
221113741940	Pipe, plastic, PVC, 4" diameter, schedule 40, includes couplings 10' OC, and hangers 3 per 10'	10.00	L.F.	\$44.86	\$448.60
221113762780	Elbow, 90 Deg., plastic, PVC, white, socket joint, 1", schedule 40	28.00	Ea.	\$23.67	\$662.76
221113762800	Elbow, 90 Deg., plastic, PVC, white, socket joint, 1-1/2", schedule 40	14.00	Ea.	\$30.67	\$429.38
221113763230	Tee, plastic, PVC, white, socket joint, 2", schedule 40	3.00	Ea.	\$46.27	\$138.81
232120581160	Hydronic heat control valve, balance and stop valve, 1" size	2.00	Ea.	\$188.33	\$376.66
312316140700	Excavating, chain trencher, utility trench, common earth, 12 HP, 8" wide, 24" deep, operator walking	1,410.00	L.F.	\$2.99	\$4,215.90
312316141700	Excavating, chain trencher, utility trench, common earth, 8" wide, 24" deep, backfill by hand, includes compaction, add	1,410.00	L.F.	\$3.89	\$5,484.90
328413100700	Subsurface drip irrigation, looped grid, pressure compensating, preinserted emitter, line, trenching and backfill	680.00	L.F.	\$1.40	\$952.00
328423101310	Underground sprinklers irrigation system, for lawns, electric remote control valve, plastic, 1", 5-30 GPM, 15-125 psi, excludes piping, excavation and backfill	3.00	Ea.	\$114.79	\$344.37

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
328423101350	Underground sprinklers irrigation system, for lawns, quick coupling valves, brass, locking cover, inlet coupling valve, 1", excludes piping, excavation and backfill	1.00	Ea.	\$225.00	\$225.00
329223101000	Sodding, bent grass sod, on level ground, over 6 M.S.F.	8.00	M.S.F.	\$637.30	\$5,098.40
Category: August 3rd Memor	ial 2-15-24 > Irrigation Subtotal				\$50,084.97
Category: August 3rd Memor	ial 2-15-24 > Landscape				
311413231520	Topsoil stripping and stockpiling, loam or topsoil, remove and stockpile on site, by skid steer, 101-500 S.Y., 6" deep, 100' haul	516.00	S.Y.	\$3.62	\$1,867.92
313116133100	Chemical termite control, herbicide, earthwork, application from truck	516.00	S.Y.	\$0.28	\$144.48
329113161050	Soil preparation, mulching, filter fabric weed barrier	516.00	S.Y.	\$1.13	\$583.08
329113161700	Soil preparation, mulching, stone mulch, quartz, hand spread	59.00	C.Y.	\$345.49	\$20,383.91
329113233100	Soil preparation, structural soil mixing, scarify subsoil, large commercial, 75 HP, dozer W/scarifier	47.00	M.S.F.	\$5.65	\$265.55
329113235000	Soil preparation, structural soil mixing, spread topsoil, skid steer loader and hand dress	72.00	C.Y.	\$21.49	\$1,547.28
329333203500	Shrubs, hydrangea, B&B, 2' - 3', planted in prepared beds	150.00	Ea.	\$96.72	\$14,508.00
329343200100	Deciduous trees, ash, balled & burlapped (B&B), 2" caliper, in prepared beds	23.00	Ea.	\$630.34	\$14,497.82
Category: August 3rd Memor	ial 2-15-24 > Landscape Subtotal				\$53,798.04
Category: August 3rd Memor	ial 2-15-24 > Electrical				
260519901250	Wire, copper, stranded, 600 volt, #10, type THWN-THHN, normal installation conditions in wireway, conduit, cable tray	6.50	C.L.F.	\$93.96	\$610.74
260519901500	Wire, copper, stranded, 600 volt, #2, type THWN-THHN, normal installation conditions in wireway, conduit, cable tray	3.80	C.L.F.	\$373.64	\$1,419.83
260533139120	PVC conduit, schedule 40, 1" diameter, to 10' H, incl terminations, fittings, & support	200.00	L.F.	\$7.38	\$1,476.00
260533139140	PVC conduit, schedule 40, 1-1/2" diameter, to 10' H, incl terminations, fittings, & support	80.00	L.F.	\$11.03	\$882.40
260590106980	Clock dial time switch, residential, 24 hour, w/enclosure, type EMT $\&$ wire, 20'	1.00	Ea.	\$243.11	\$243.11
260926100270	Room controller, dimming, 3 relay	1.00	Ea.	\$1,940.25	\$1,940.25
262416202004	Circuit breakers, 120/240 volt, plug-in, 1 pole with NM cable, 20 amp	5.00	Ea.	\$87.16	\$435.80
262416300300	Panelboards, 1 phase 3 wire, main lugs, 120/240 V, 100 amp, 20 circuits, NQ, incl 20 A 1 pole bolt-on breakers	1.00	Ea.	\$2,328.56	\$2,328.56
262713100600	Meter socket, double position, 4 terminal, 150 A	1.00	Ea.	\$574.66	\$574.66
262816400700	Time switches, photo cell, 2,000 watt	1.00	Ea.	\$84.27	\$84.27
262913100900	Lighting contactors, 3 pole, mechanically held, 600 volt, 60 amp, NEMA	2.00	Ea.	\$1,838.55	\$3,677.10

LineNumber	Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
263113500390	Photovoltaic components, combiner box, 10 lug, NEMA 3R enclosure	1.00	Ea.	\$492.97	\$492.97
265613100100	Exterior, light poles, concrete, 30' above 5' below, 13.5" Base, 5.5" Tip	1.00	Ea.	\$2,641.41	\$2,641.41
265626200280	Landscape fixtures, recessed uplight, incandescent, 300 W, incl conduit, wire, trench	23.00	Ea.	\$916.81	\$21,086.63
312316140750	Excavating, chain trencher, utility trench, common earth, 12 HP, 8" wide, 36" deep, operator walking	560.00	L.F.	\$3.50	\$1,960.00
312316141750	Excavating, chain trencher, utility trench, common earth, 8" wide, 36" deep, backfill by hand, includes compaction, add	560.00	L.F.	\$5.78	\$3,236.80
Category: August 3rd Memorial	2-15-24 > Electrical Subtotal				\$43,090.53
Subtotal					\$468,204.09
General Contractor's Markup on	n Subs			0.00%	\$0.00
Subtotal					\$468,204.09
General Conditions				0.00%	\$0.00
Subtotal					\$468,204.09
General Contractor's Overhead a	and Profit			31.90%	\$149,357.10
Grand Total					\$617,561.19

Sheet NumberSheet DescriptionTimestampG-000Cover Sheet17-Mar-23G-101General Notes / Code Data26-Jan-23G-102Arial Concept View6-Dec-22Topographic Survey11-May-22C-101General Notes / Code Data2-Feb-23C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details6-Dec-22A-503Flat-Work Details6-Dec-22A-503Flat-Work Details6-Dec-22A-504Sculpture Details6-Dec-22A-505Sculpture Details6-Dec-22A-506Sculpture Details6-Dec-22A-507Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23<		Appendix B	
G-101General Notes / Code Data26-Jan-23G-102Arial Concept View6-Dec-22Topographic Survey11-May-22C-101General Notes / Code Data2-Feb-23C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Notes4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-101Landscape General Notes30-Mar-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	Sheet Number	Sheet Description	Timestamp
G-102Arial Concept ViewG-Dec-22Topographic Survey11-May-22C-101General Notes / Code Data2-Feb-23C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-101Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Plan30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-503Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	G-000	Cover Sheet	17-Mar-23
Topographic Survey11-May-22C-101General Notes / Code Data2-Feb-23C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-501Planting Details30-Mar-23L-502Irrigation Plan30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	G-101	General Notes / Code Data	26-Jan-23
C-101General Notes / Code Data2-Feb-23C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape General Notes30-Mar-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23A-503Flat-Work Details30-Mar-23S-500Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	G-102	Arial Concept View	6-Dec-22
C-102Striping Specifications4-Nov-22C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Demo / Improvement Floor Plan30-Mar-23A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23		Topographic Survey	11-May-22
C-103Grading Plan12-Feb-24C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-101	General Notes / Code Data	2-Feb-23
C-104Stormwater Pollution Prevention Plan27-Feb-23C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-501Planting Details30-Mar-23L-502Irrigation Plan30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-102	Striping Specifications	4-Nov-22
C-105Stormwater Pollution Prevention Plan Details4-Nov-22C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Demo / Improvement Floor Plan30-Mar-23A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-103	Grading Plan	12-Feb-24
C-106Stormwater Pollution Prevention Plan Notes4-Nov-22L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Demo / Improvement Floor Plan30-Mar-23A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-104	Stormwater Pollution Prevention Plan	27-Feb-23
L-100Landscape General Notes30-Mar-23L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-105	Stormwater Pollution Prevention Plan Details	4-Nov-22
L-101Landscape Plan5-Dec-23L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	C-106	Stormwater Pollution Prevention Plan Notes	4-Nov-22
L-102RPlant Images2-Feb-23L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-100	Landscape General Notes	30-Mar-23
L-103Irrigation Plan30-Mar-23L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-101	Landscape Plan	5-Dec-23
L-501Planting Details30-Mar-23L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-102R	Plant Images	2-Feb-23
L-502Irrigation Details30-Mar-23A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-103	Irrigation Plan	30-Mar-23
A-100Site Plan6-Dec-22A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-501	Planting Details	30-Mar-23
A-101Enlarged Site Plan30-Mar-23A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	L-502	Irrigation Details	30-Mar-23
A-102Demo / Improvement Floor Plan30-Mar-23A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-100	Site Plan	6-Dec-22
A-500Sculpture Details6-Dec-22A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-101	Enlarged Site Plan	30-Mar-23
A-501Details6-Dec-22A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-102	Demo / Improvement Floor Plan	30-Mar-23
A-502Pilars Legend27-Feb-23A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-500	Sculpture Details	6-Dec-22
A-503Flat-Work Details30-Mar-23S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-501	Details	6-Dec-22
S-000Structural Notes27-Feb-23S-101Foundation Plan20-Oct-22S-301Framing Sections & Details27-Feb-23	A-502	Pilars Legend	27-Feb-23
S-101 Foundation Plan 20-Oct-22 S-301 Framing Sections & Details 27-Feb-23	A-503	Flat-Work Details	30-Mar-23
S-301 Framing Sections & Details 27-Feb-23	S-000	Structural Notes	27-Feb-23
5	S-101	Foundation Plan	20-Oct-22
E-100R1 Electrical General Notes 2-Feb-23	S-301	Framing Sections & Details	27-Feb-23
	E-100R1	Electrical General Notes	2-Feb-23
E-200R2 Electrical Plan 27-Feb-23	E-200R2	Electrical Plan	27-Feb-23
E-300 Electrical Details 20-Oct-22	E-300	Electrical Details	20-Oct-22
E-400 Electrical Schedules 27-Feb-23	E-400	Electrical Schedules	27-Feb-23
Specifications 5-Dec-23		Specifications	5-Dec-23